



V. R. ELPHINSTONE
PROPOSED COMBINED
BOOKING OFFICE AND SIGNAL BOX
"UP" PLATFORM.
Scales - as shown.

Chief Civil Engineer.

Work Completed	H. S. H. H.	S.B. 2235	PLAN No
Drawn by	Checked by	Corres. No	1919/20
27.	31. 5. 1940.	A. 23.	271-40

NOTE - SEE SHEET No. 2. PLAN No. 271 FOR DETAILS OF OFFICE FITTINGS, LOBBY FLOOR, FIREPLACE AND ETC.
CONCRETE FOR FOUNDATIONS SHALL CONSIST OF 5 PARTS OF 1 1/2 CRUSHED BLUESTONE, 3 PARTS OF COARSE SAND, 1 PART OF PORTLAND CEMENT. TO BE REINFORCED WITH MID GAUGE, 6"x6" MESH STEEL WIRE FABRIC.
MORTAR FOR BRICKWORK SHALL CONSIST OF 3 PARTS OF SAND, 2 PARTS OF HYDRATED LIME, 1 PART OF PORTLAND CEMENT.
CEILINGS TO BE INSULATED BETWEEN JOISTS WITH INFUL-WOOL TO A DEPTH OF 2". TO BE PROTECTED FROM DUST WITH LAYER OF BUILDING PAPER OVER JOISTS.